

STANDARD OPERATING PROCEDURE

Title: Blast Furnace Cooling Circuit Inspection

Document ID: SOP-BF-001

Procedure

1. Verify cooling water flow.
2. Measure inlet temperature.
3. Measure outlet temperature.
4. Inspect pumps.
5. Verify pressure stability.
6. Check for leakage.

Failure Indicators

- Reduced flow rate
- Elevated furnace shell temperature
- Pump vibration increase